



P.O. Box 2098 • Georgia, Vermont 05468
www.harrisonconcreteinc.com

KEVIN J. HARRISON, President
JAMES A. HARRISON, Vice President
JANET A. HARRISON, Vice President

April 10, 2023

South Hero, VT
South Hero sand and salt shed

Scope of work

Please find the following price for concrete in place for the above job as discussed with John Beulac on site. This price is good for this scope and this scope only. Any changes will add or deduct accordingly.

Detailed scope of work:

Inclusions:

- All necessary concrete
- All labor to form, place and finish
- Supply and install required reinforcing
- Provide concrete pumping as needed

Items Included:

- 1) Footings
 - a. Approximately 280 lineal feet of 8' X 1' with reinforcing @ 40'x100' salt shed
 - b. Approximately 140 lineal feet of 2' X 1' with reinforcing @ south lean to
 - c. Approximately 60 lineal feet of 3' X 1' with reinforcing @ push wall
- 2) Wall
 - a. Approximately 256 lineal feet of 16' X 15" with reinforcing @ 40'x100' salt shed
 - b. Approximately 24 lineal feet of 3' X 15" with reinforcing @ salt shed door wall
 - c. Approximately 140 lineal feet of 5' X 8" with reinforcing @ south lean to
 - d. Approximately 60 lineal feet of 8' X 1' with reinforcing @ push wall
- 3) Isolated footings
 - a. 6 locations
 - b. 3' X 3' X 1' with reinforcing @ north lean to
- 4) Isolated piers
 - a. 6 locations
 - b. 14" X 14" X 4' with reinforcing
- 5) Slabs on grades
 - a. Approximately 4,000 square feet 8" thick with reinforcing @ 40'x100' salt shed
 - b. Approximately 3,200 square feet 8" thick with reinforcing @ 40'x200' apron

(802) 849-6688

FAX (802) 849-9768

Sent to Doris' email
10/9/23

HARRISON CONCRETE CONST. INC.

P.O. Box 2098 • Georgia, Vermont 05468
www.harrisonconcreteinc.com

KEVIN J. HARRISON, President
JAMES A. HARRISON, Vice President
JANET A. HARRISON, Vice President

- c. Saw cuts as necessary
- d. Cured and sealed

LUMP SUM COMPLETE\$289,000.00

Exclusions:

- 1) Miscellaneous embedded metals
- 2) Housekeeping pads
- 3) Specialty wall finish (form finish only)
- 4) Penetrations (supplied by others)
- 5) Winter concrete
- 6) Winter protection
- 7) All rigid insulation
- 8) Specialty slab finishes
- 9) Waterproofing
- 10) Dewatering
- 11) All site concrete
- 12) All sealing of concrete not listed above
- 13) Filling of saw cuts

(no slabs @ north and south fronts)

Thank you,

Kevin Harrison (DC)

Kevin Harrison, President
Harrison Concrete Construction, Inc.

Ross Brown 10/9/23
ROSS BROWN
VICE-CHAIR SELECT BOARD

(802) 849-6688

FAX (802) 849-9768

doris@harrisonconcreteinc.com